4-20--26 Road Name	ODOT No.	Route Begin	End Route	ROADWAY Calculated Length	Measured Length	Average Width	Area	Depth Item 448 Intermediate Course	Depth Item 448 Surface Course	202 Curb Removed, As per plan	251 Partial Depth Repair, As Per Plan	254 Pavement Planing, As Per Plan	254 Pavement Planing - Butt Joints, As Per Plan	254 Pavement Planing - Butt Joints (Driveway), As Per Plan	407 Non Tracking Tack (0.08 Gal/SY)	411 Stabilized Crushed Limestone, As Per Plan	422 Fog Seal @ 0.15 Gal/SY, As Per Plan	422 Single Chip Seal MC-3000, No. 8, As Per Plan	422 Single Chip Seal MC-3000, No. 67, screened w/ No. 8	441 Asphalt Concrete Intermediate Course, Type 1 (448)	441 Asphalt Concrete Surface Course, Type 1 (448) PG 64-22	608 Curb Ramps	609 Curb and Gutter, Type 3, As per plan	611 Manhole Adj. To Grade, As per plan	638 Water Valve Adj. To Grade, As per plan	614 Work Zone Centerline Class 1	642 Edge Line, 4"	642 Centerline	642 Stop Line	642 Railroad Symbol Marking, 96"
				Miles	Feet	Feet	Sq. Yds	Inches	Inches	LF	Sq. Yds	Sq. Yds	Each	Each	Gals.	Tons	Sq. Yds	Sq. Yds	Sq. Yds	Tons	Tons	Each	LF	Each	Each	Miles	Miles	Miles	Feet	Each
Mad River Township																														
Wakefield incl. Jacobs Ct.	T-1613	Westcott	End Route	0.39	2,055	27	6,165.00	1/2	1 1/4	250	50	6,300			900					175	450		250	18	6					
Kimmel	T-1582	Hahn	End Route	0.13	660	27	1,980.00	1/2	1 1/4	100	50	2,000			300					65	150		100	10	6					
Danzig	T-1583	Kimmel	Culdesac	0.06	300	27	900.00	1/2	1 1/4	50	50	1,000			140					30	75		50	2	1					
Pheasant Hill	T-1716	Kings Ridge	Culdesac	0.10	505	27	1,515.00	1/2	1 1/4		50	1,700			225					50	125			3	2					
Steeplechase	T-1717	Count Ridge	Kings Ridge	0.18	950	27	2,850.00	1/2	1 1/4		50	6,300			1,000					450	1,000			4	3					
			Subtotals	**0.86**			**13,410.00**			**400**	**250**	**17,300**			**2,565**					**770**	**1,800**		**400**	**37**	**18**					